PROJECT AT A GLANCE















SPML INFRALTD.

SPML Infra is a leading infrastructure development company of India. An ISO–9001:2008 certified, it has executed almost 600 turnkey projects and created significant value with the provision of drinking water, improved sewerage facilities, better municipal waste management, building roads and highways and lighting up homes over the last three decades. SPML is currently executing infrastructure projects worth Rs. 8000 Crore in India.

OM METALS INFRAPROJECTS LTD.

Om Metals Infraprojects, established in 1971 is a pioneer in execution of turnkey hydro mechanical projects involving major hydro power and irrigation projects in India and abroad. An ISO 9001:2008 company, it has completed more than 50 projects with design, engineering, manufacture, supply, erection, testing and commissioning. It is currently executing a number of large infrastructure projects in India and abroad.



SPML Infra Limited

Corporate Office: SPML House, Plot No. 65, Sector-32, Institutional Area, Gurgaon - 122001, Haryana Tel: +91-124-3944555 Fax: +91-124-3983201 info@spml.co.in, www.spml.co.in



Om Metals Infraprojects Limited

NBCC Plaza, Tower-III, 4th Floor, Pushp Vihar- Sector 5, Saket, New Delhi – 110017 Tel: + 91- 11- 45960000 Fax: +91- 11-29565551 info@ommetals.com, www.ommetals.com



Kalisindh Concrete Gravity Dam

A Celebration Series Of SPML's Signature Projects



PROJECT AT A GLANCE

Kalisindh Major Concrete Gravity Dam located on River Kalisindh in Jhalawar district of Rajasthan was planned to develop a storage dam to meet 34 Million Cubic Meter (MCM) water requirements for 1200 MW Kalisindh Super Thermal Power Plant located in Jhalawar District of Rajasthan for Rajasthan Rajya Vidyut Utpadan Nigam Limited. The work of Construction of Dam was awarded by Water Resources Department, Rajasthan to SPML Infra Limited and its JV partner Om Metals Infraprojects Limited on EPC Turnkey Project basis on 30.04.2010 with project cost of Rs. 457.21 Crores.

| | Description | Details in Brief |
|---|--|--|
| | Name of the Project | Construction of Kalisindh Dam on EPC Turnkey Project basis. |
| | Client | Water Resources Department, Government of Rajasthan |
| : | Contract Value Design-Build O&M Total | 454.81 Crore 002.40 Crore 457.21 Crores |
| | Scope of Work | Construction of civil, hydro-mechanical & electrical works of Kalisindh Gravity Dam under Single point responsibility turnkey job basis including 2 years of O&M |
| | Planning | Review of hydrology, topographical survey, fixing of dam-axis, preparation of DPR and approval of DPR from Central Water Commission, New Delhi. |
| | Design | Design and preparation of construction drawings of spillway, abutments, wing walls, stilling basin, Radial Gates and all other auxiliary works and their approval from Central Water Commission. |
| | Civil Works | Constructed 995 meter long, 26 meter high concrete gravity dam to store 54 MCM water at F.R.L.316.00M |
| | Hydro mechanical works | Fabrication, erection and commissioning 33 numbers radial gates of size 15Mx10.5M with 250 tonnes hydraulic hoist lifting arrangements for design discharge of 32411Cumecs |
| | Control Room & Electrical works | Construction of control Room with atomized operation of gates from control room |

THE SCOPE OF WORK

- Review of hydrology, topographical survey, fixing of dam-axis, preparation of DPR and approval of DPR from Central Water Commission, New Delhi.
- Design and preparation of construction drawings of spillway, abutments, wing walls, stilling basin, radial gates and all other auxiliary works and their approval from Central Water Commission.
- Construction of dam and hydro-mechanical works as per approved drawings from CWC.

drawings from CWC, concrete gravity dam was constructed, 995 meter long, 26 meter high to store 54 MCM water at F.R.L.316.00M with flood discharging arrangement of 32411 Cumecs provided by 33 Numbers Radial Gates of size 15 Mtrs X 10.5 Mtrs with 250 Tonne years for completion. Hydraulic Hoist Lifting arrangements.

The work from concept to completion of such a major dam with hydro-mechanical works was completed by SPML Infra & Om Metals Infraprojects within 4 years, in spite of the fact that the work was delayed / stopped several times due to forest clearance and by the local residents for want of compensation. The timely support by the client, Rajasthan Water Resources Department made it possible

After the necessary approval of DPR & construction to complete the dam construction in record time and filling of water in reservoir begin on 22 July 2014.

> This is first time in the history of the Rajasthan that such a large Dam has been completed in such a short period, otherwise in past all the Major & Medium dams took 15-20

> SPML adopted the latest technology for rapid dam construction i.e. 132 ft. long Telebird concrete placer with 50 Cum/hr. placing capacity, automatic weigh batching plants, cranes, hippo, haul pack dumpers, high capacity excavators, loaders, drilling & grouting equipment's, dewatering pumps with fully equipped workshop for fabrication & erection of radial gates at Dam site with international standards. The hydraulic hoists of 250 tonne lifting capacity were imported from Germany.

HYDROLOGY

| Description | Figures |
|----------------------------------|------------|
| Gross catchment area | 7547 Sq-k |
| Catchment area in M.P.State | 6685 Sq-km |
| Catchment area in Rajasthan | 862 Sq-km |
| Estimated annual yield at | 147 MCM |
| 75% dependability | |
| Proposed Gross storage capacity | 54.37MCM |
| Dead storage capacity | 0.17MCM |
| Live storage capacity of the dam | 54.20MCM |

GATES

| Description | Figures |
|----------------------|------------|
| No. of gates | 33 |
| Size of Radial gates | 15Mx10.5 M |
| Crest level | 306 M |

SUBMERGENCE

| Description | Figures |
|--|---------|
| Total area in Submergence at FRL 316.00M | 1834 Ha |
| Number of villages in submergence | 26 nos |

QUANTITY EXECUTED

| Item | Total |
|-------------------------|--------------|
| Excavation - Earth Work | 375741 Cum |
| Excavation in Hard Rock | 1106544 Cum |
| Cement Concrete | 202567 Cum |
| Reinforcement | 4611 MT |
| Drilling | 16254 Meters |
| Grouting | 171 MT |

DAM & SPILLWAY

| Description | Figures | | | |
|--|--------------|--|--|--|
| Full reservoir level (FRL) | 316.0 M | | | |
| Maximum water level (MWL) | 316.0 M | | | |
| Free board (FB) | 6.00 M | | | |
| Top Bund Level (TBL) | 322.0 M | | | |
| Foundation level | 294.5 M | | | |
| Probable maximum flood discharge (PMF) | 32411 Cumecs | | | |
| Total length of dam | 995M | | | |
| Length of over flow | 607M | | | |
| Length of non over flow | 389M | | | |
| Minimum draw down level | 306M | | | |
| Type of spillway | Oghee | | | |
| | | | | |

